

**Berrien County Road Commission
LCT 2007 Cape Seal Program
Project 641**

Road Name	Yr. Last Sealed	Width (ft)	Length (ft)	Area (SFT)	No. of Radii	Area of Radii	Cul-de-sac	Area	Total SFT	Total SYD
Anderson Circle	1994	28	2118	59304	4	86		0	59,390	6,599
Country Knoll PI	1993	28	1105	30940	2	43	48	7,238	38,221	4,247
Old Farm Lane	1998	28	1080	30240	2	43	54	9,161	39,444	4,383
Grandwood Circle	1998	30	2520	75600	4	86		0	75,686	8,410
Michigan Ave *	No record	16	1127	18032	4	86		0	18,118	2,013
Lakewood Ave *	No record	11	1130	12430	2	43		0	12,473	1,386
Notre Dame Ave *	No record	16	1125	18000	2	43		0	18,043	2,005
Brookfield Dr **	2000	19.5	1348	26286	4	86		0	26,372	2,930
Meadow Ln **	2000	20	2178	43560	4	86		0	43,646	4,850
Greenfield **	2000	18	867	15606	4	86		0	15,692	1,744
Dennis St	1999	20	1294	25880	2	43		0	25,923	2,880
Donald St	1999	20	1295	25900	2	43		0	25,943	2,883
John St	1999	15	125	1875	2	43		0	1,918	213
John St	1999	16.5	426	7029	6	129		0	7,158	795
Ponderosa Dr	1999	20	2556	51120	4	86		0	51,206	5,690
Longhorn Trail	1999	20	1192	23840	4	86		0	23,926	2,658
Bonanza Dr	1999	20	1333	26660	8	172		0	26,832	2,981
Clearbrook Dr	1999	19.5	1367	26656.5	2	43		0	26,700	2,967
Brook Point Ln	1999	20.5	1553	31836.5	2	43		0	31,880	3,542
Niagara Circle	1992	29.5	720	21240	2	43	45	6,362	27,645	3,072
Fredonia Circle	1992	30	400	12000	2	43	45	6,362	18,405	2,045
Defay Rd	1992	20.5	467	9573.5	2	43		0	9,617	1,069
Chicago Ave.	No record	Regravel	Cost of \$2,475 pd. for from BCRC matching funds							
TOTAL LENGTH			27,326 ft.							

* Single Seal and Slurry Seal. All other roads, cape seal only. Bids will be taken 5/10.
 ** Brookfield, Meadow Ln., Greenfield were damaged due to storm sewer work completed last spring

Twp. Board Approved Road Projects for 2007		Cost:
Rockey Weed Repave from Clev. To Wash.		\$76,000
Pave shoulders from G' Lord to Maiden Ln. along Wash. Ave.		\$34,800
Twp. Subdivision Cape Seal Budget		\$35,000
Total Twp. '07-'08 Budget for road upgrade and maint.		\$145,800
BCRC Contribution		\$58,600
Total Cost of 2007 LCT Road Work		\$204,400

The paved shoulders along Wash. Ave. are being done in conjunction with BRRC repave. This work will begin July 9.
 This year's Cape Seal costs are \$18,070/mile, this compares to \$100,000/mile to replace these roads.